

HIGHWAY SALT SHED ROOF

BID SPECIFICATIONS

1. ALL MATERIALS, EQUIPMENT AND LABOR TO BE INCLUDED IN THE PRICE.
2. PROPER SAFETY EQUIPMENT MUST BE USED SUCH AS HARD HATS, TIE OFFS, HARNESSSES AND MAN LIFTS.
3. BIDDERS SHOULD GET THEIR OWN ACCURATE MEASUREMENTS PRIOR TO MAKING A BID.
4. BIDDER MUST BE OSHA COMPLIANT.
5. ALL WAGES ARE TO BE PAID AT PREVAILING RATE
6. TWO MILLION DOLLAR LIABILITY INSURANCE AND WORKERS COMPENSATION INSURANCE IS REQUIRED.

INSTALLATION OF NEW ROOFING OVER THE HIGHWAY DEPARTMENT SALT SHED, REPAIRS TO THE FACIA WHERE NEEDED AND COVERING THE FACIA WITH ALUMINUM.

MATERIAL TO INCLUDE:

- 44' X 66' / 22' TO PEAK
- 2x4 NAILERS OVER SHINGLES
- 50 YEAR , 20 GUAGE STEEL, COLOR BROWN

1) STEEP-SLOPE ROOF SHEET METAL FABRICATION

- (a) Apron, Step, Cricket and Backer Flashing: Fabricate from the following material:
 - (i) Aluminum: 0.0320 inch thick.
- (b) Drip Edges: Fabricate from the following material:
 - (i) Aluminum: 0.0320 inch thick.
- (c) Eave, Rake Flashing: Fabricate from the following material:
 - (i) Aluminum: 0.0320 inch thick.

2) SHEET METALS

- (a) Aluminum Sheet: ASTM B 209, Alloy 3003, 3004, 3105, or 5005, Temper suitable for forming and structural performance required, but not less than H14, finished as follows:
 - (i) HIGH-PERFORMANCE ORGANIC FINISH: Two Coat, Thermocured system containing not less than 70 percent polyvinylidene fluoride resin by weight; complying with AAMA 2604.
 1. Color: As selected by architect from manufacturer's full range

ALL MATERIALS TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN SPECIFICATIONS